

Atlantic Testing Laboratories
LIMITED

SECTION 1

**SUBSURFACE INVESTIGATION
FORT FAIRFIELD, ME**

**CONTRACT DACW-33-85-D-0011
CONTRACTING OFFICER:
Edward D. Hammond, LTC, CE
28 June 1985**

**DELIVERY ORDER NO. 0009
5 MARCH 1986**

**PREPARED FOR: U.S. Army Corps of Engineers
New England Division
424 Trapelo Road
Waltham, MA 02254-9149**

**PREPARED BY: Theresa A. Beddoe
Atlantic Testing Laboratories, Limited
P. O. Box 29
Canton, NY 13617**

March 18, 1986

ATL Report No. CD013-1-3-86

SECTION 2

TABLE OF CONTENTS

SECTION 1	Title Page
SECTION 2	Table of Contents
SECTION 3	Scope of Investigation <ul style="list-style-type: none">a. Delivery Orderb. Project Sitec. Purposed. Authoritye. Scope of Work
SECTION 4	Quality Control <ul style="list-style-type: none">a. General Certification Statementb. Records Takenc. Equipment Usedd. Procedures
SECTION 5	Summary of Activities and Telephone Log <ul style="list-style-type: none">Table I Summary of ActivitiesTable II Telephone Log
SECTION 6	Chain of Custody Logs
SECTION 7	Safety Reports
SECTION 8	Field Inspector's Logs <ul style="list-style-type: none">a. Figure 1 - General Project Mapb. Figure 2 - Site Location Mapc. Figure 3 - Boring Location Pland. Boring Logs

SECTION 3

SCOPE OF INVESTIGATION

- a. Delivery Order No. 0009**

<input type="checkbox"/> CHECKED BOX APPLIES		<input type="checkbox"/> ORDER FOR SUPPLIES OR SERVICES		<input type="checkbox"/> REQUEST FOR QUOTATIONS NO. RETURN COPIES OF THIS QUOTE BY (THIS IS NOT AN ORDER. See DD Form 1155r)		PAGE 3 OF 2																															
1. CONTRACT/PURCH ORDER NO. DACW33-85-D-0011		2. DELIVERY ORDER NO. 0009		3. DATE OF ORDER 86 MAR 05		4. REQUISITION/PURCH REQUEST NO. GEB 86-28																															
5. ISSUED BY Dept. of the Army New England Division, Corps of Engineers 424 Trapelo Road Waltham, MA 02254-9149 Buyer/Symbols: Hebart/NEDSD-P Phone: AC 617/647-8207				7. ADMINISTERED BY: (If other than 6) CODE		8. CERTIFIED FOR NATIONAL DEFENSE UNDER DMS REG 1 DO																															
6. CONTRACTOR/QUOTER Atlantic Testing Laboratories, Ltd. P.O. Box 29 Canton, NY 13617				7. FACILITY CODE		8. DELIVERY FOR <input checked="" type="checkbox"/> DEST <input type="checkbox"/> OTHER (See Schedule if other)																															
10. DELIVER TO FOB POINT BY: In Accordance with Paragraph 7 of Attachment NET				11. CHECK IF BUSINESS IS <input checked="" type="checkbox"/> SMALL <input type="checkbox"/> SMALL DISADVANTAGED <input type="checkbox"/> WOMEN-OWNED		13. MAIL INVOICES TO Finance & Accounting Officer at issuing office																															
14. SERVICES FOR: U.S. Army Engineer Division, New England ATTN: Geotechnical Engineering Branch 424 Trapelo Road Waltham, MA 02254-9149				15. PAYMENT WILL BE MADE BY: Finance & Accounting Officer at issuing office		MARK ALL PACKAGES AND PAPERS WITH CONTRACT OR ORDER NUMBER																															
16. TYPE OF ORDER DELIVERY <input checked="" type="checkbox"/> PURCHASE <input type="checkbox"/>		This delivery order is subject to instructions contained on this side of form only and is issued on another Government contract or in accordance with and subject to terms and conditions of above numbered contract. Reference your _____ furnish the following on terms specified herein, including, for U.S. purchases. General Provisions of Purchase Order on DD Form 1155r (EXCEPT CLAUSE NO. 12 APPLIES ONLY IF THIS BOX <input type="checkbox"/> IS CHECKED, AND NO. 14 IF THIS BOX <input type="checkbox"/> IS CHECKED); special provisions _____ and delivery as indicated. This purchase is negotiated under authority of 10 USC 2304(a)(3) or as specified in the schedule if within the U.S., its possessions or Puerto Rico; if otherwise under 2304(a)(6). <input type="checkbox"/> If checked, Additional General Provisions apply: Supplier shall sign "Acceptance" on DD Form 1155r and return _____ copies																																			
17. ACCOUNTING AND APPROPRIATION DATA/LOCAL USE 96X3122 Construction General BE81930720E00000(MC)						SB GEB AE/PS Coord JJH/ckh																															
CONTRACT <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>16. ITEM LINE</th> <th>19. SCHEDULE OF SUPPLIES/SERVICES</th> <th>20. QUANTITY ORDERED/ACCEPTED*</th> <th>21. UNIT</th> <th>22. UNIT PRICE</th> <th>23. AMOUNT</th> </tr> </thead> <tbody> <tr> <td></td> <td>Furnish necessary services and equipment to provide subsurface investigations adjacent to Aroostook River for proposed dike improvement project, Ft. Fairfield, ME.</td> <td>APPROX.</td> <td></td> <td></td> <td>ESTIMATED</td> </tr> <tr> <td>1.2</td> <td>Geotechnical Inspector</td> <td>84</td> <td>HR</td> <td>\$40.00</td> <td>\$3,360.00</td> </tr> <tr> <td>1.3</td> <td>Per Diem - overnight stay</td> <td>9</td> <td>DAY</td> <td>45.00</td> <td>405.00</td> </tr> <tr> <td>1.4</td> <td>Mileage from Waltham, MA and return</td> <td>800</td> <td>MI</td> <td>.35</td> <td>280.00</td> </tr> </tbody> </table>								16. ITEM LINE	19. SCHEDULE OF SUPPLIES/SERVICES	20. QUANTITY ORDERED/ACCEPTED*	21. UNIT	22. UNIT PRICE	23. AMOUNT		Furnish necessary services and equipment to provide subsurface investigations adjacent to Aroostook River for proposed dike improvement project, Ft. Fairfield, ME.	APPROX.			ESTIMATED	1.2	Geotechnical Inspector	84	HR	\$40.00	\$3,360.00	1.3	Per Diem - overnight stay	9	DAY	45.00	405.00	1.4	Mileage from Waltham, MA and return	800	MI	.35	280.00
16. ITEM LINE	19. SCHEDULE OF SUPPLIES/SERVICES	20. QUANTITY ORDERED/ACCEPTED*	21. UNIT	22. UNIT PRICE	23. AMOUNT																																
	Furnish necessary services and equipment to provide subsurface investigations adjacent to Aroostook River for proposed dike improvement project, Ft. Fairfield, ME.	APPROX.			ESTIMATED																																
1.2	Geotechnical Inspector	84	HR	\$40.00	\$3,360.00																																
1.3	Per Diem - overnight stay	9	DAY	45.00	405.00																																
1.4	Mileage from Waltham, MA and return	800	MI	.35	280.00																																
* If quantity accepted by the Government is same as quantity ordered, indicate by ✓ mark. If different, enter actual quantity accepted below quantity ordered and encircle		24. UNITED STATES OF AMERICA BY: EDWARD D. HAMMOND Lt. Colonel, Deputy Division Engineer				25. TOTAL \$13,330.00																															
26. QUANTITY IN COLUMN 20 HAS BEEN <input type="checkbox"/> INSPECTED <input type="checkbox"/> RECEIVED <input type="checkbox"/> ACCEPTED, AND CONFORMS TO THE CONTRACT EXCEPT AS NOTED DATE _____ SIGNATURE OF AUTHORIZED GOVERNMENT REPRESENTATIVE _____		27. SHIP NO <input type="checkbox"/> PARTIAL <input type="checkbox"/> FINAL		28. DO VOUCHER NO. 32. PAID BY		30. INITIALS 33. AMOUNT VERIFIED CORRECT FOR																															
35. I certify this account is correct and proper for payment. DATE _____ SIGNATURE AND TITLE OF CERTIFYING OFFICER _____		31. PAYMENT <input type="checkbox"/> COMPLETE <input type="checkbox"/> PARTIAL <input type="checkbox"/> FINAL		34. CHECK NUMBER		36. BILL OF LADING NO.																															
37. RECEIVED AT		38. RECEIVED BY		39. DATE RECEIVED		40. TOTAL CONTAINERS																															
41. S/R ACCOUNT NUMBER		42. S/R VOUCHER NO																																			

CONTINUATION SHEET

REF NO OF DOC. BEING CONT'D.

Delivery Order 0009 to

Contract No. DACW33-85-D-0011

PAGE

2

OF

2

OF OFFEROR OR CONTRACTOR

CONTRACT

ATLANTIC TESTING LABORATORIES

LINE ITEM NO.	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
		APPROX.			ESTIMATED
2.1	Geotechnical Report	1	JOB	60% of 1.2	\$2,016.00
6.1	Mobilization and Demobilization	1	JOB	\$700.00	700.00
6.3	Mileage from/to contractor's main equipment storage site	660	MI	1.15	759.00
6.5	Standby time/on site moves	24	HR	75.00	1,800.00
13.1	0 - 30 Ft. depth	36	EA	13.00	468.00
13.2	31 - 50 Ft. depth	2	EA	16.00	32.00
8.1	BX, NX Size	155	LF	18.00	2,790.00
22.3	NWX Size and/or NWM	16	LF	45.00	720.00

ATTACHMENT NO. 1

GEB REQUISITION NO. 86-28, DELIVERY ORDER NO. 0009

CONTRACT NO. DACW 33-85-D-0011

INSPECTION AND EXPLORATION INSTRUCTIONS

PROJECT: Fort Fairfield Local Protection Project

SITE: Fort Fairfield, Maine

AUTHORITY: The Fort Fairfield Local Protection Project is funded under authority of Section 205 of the 1948 Flood Control Act.

PURPOSE: The subsurface investigations are to determine the foundation conditions adjacent to the Aroostook River for the proposed dike improvement project.

1. SCOPE OF INVESTIGATION

a. Locate seven (7) drive sample - SPT borings by means of taping the given distances as indicated on Attachment No. 2. Elevations for the borings will be estimated based on the contours shown on Attachment 2.

b. The seven drive sample - SPT borings shall be driven to the depths as follows: A-32', B-32', C-17', D-12', E-32', F-32', and G-22'. The sampling work shall be in accordance with paragraph 13, page C-21 of the specifications. The entire sample for each SPT drive shall be saved and placed in as many jars as required. Where refusal is encountered before depth is attained in a borehole, the boring shall be continued using vertical diamond core drilling. If the material causing refusal is not penetrated within five feet of the original refusal elevation, the boring shall be terminated. Refusal is defined as 100 blows with a less than 12" penetration or bouncing refusal.

c. A geotechnical inspector shall act as field inspector while performing the borings. The inspector shall provide telephone reports to Mr. Blair, Corps of Engineers, at 617-647-8396 at least once a day.

d. All samples shall be delivered to the Corps of Engineers Headquarters in Waltham, Massachusetts by the field inspector. Sample delivery shall be coordinated with the Director, NED Materials and Water, Quality Laboratory at 617-647-8357/8392.

2. SITE CONDITIONS

The proposed exploration program is adjacent to the Aroostook River in Fort Fairfield, Maine. The proposed explorations are on relatively flat areas, except for possibly FD-C.

3. RIGHTS OF ENTRY

The rights of entry have been obtained from the Town of Fort Fairfield and the Canadian Pacific Railroad (copies attached). The contractor is

responsible for contacting the town and railroad to notify them when the work is to be done. The individuals to be contacted are:

Alphonse R. Dixon
Town Manager
Town of Fort Fairfield
P. O. Box 451
Fort Fairfield, ME 04742
(207) 472-3801

M. S. Andrews
Supt. of Canadian Pacific Railway
Canadian Pacific Railway
Box 3460
Station B
St. John, New Brunswick E 2M4x2
(506) 635-2200

The contractor is also responsible for obtaining a flagman, if one is required by the Canadian Pacific Railway.

4. COORDINATION

Mr. J. Blair, Corps of Engineers, 617-647-8396, shall be contacted five days prior to start of work and at least once a day by the geotechnical inspector to report on how work is progressing and what types of materials are being encountered.

5. EXPLORATION NUMBERS

The drive boring locations as shown on Attachment No. 2 and designated A-G shall be numbered FD-86-7 through FD-86-13 in order of their completion. The new numbers shall be indicated on the boring logs and shown on a plan of explorations.

6. GOVERNMENT REVIEW

The Government will review the draft submittal as well as the completed work. Subsequent to such review, the Contractor shall accomplish any corrections which may be directed as the result of the Government review.

7. COMPLETION SCHEDULE

Services under this delivery order shall start within 15 calendar days after receipt of delivery order. Duration of the drilling effort is estimated to be seven work days. The geotechnical report shall be submitted in draft format for review (by the Government), postmarked no later than seven calendar days after completion of the field work. Government review will take approximately ten calendar days from receipt of draft report. The final geotechnical report shall be submitted postmarked no later than seven calendar days after receipt of draft report with Government comments.

8. QUALITY CONTROL

You will be held responsible for the quality of the maps submitted and for all damages caused the Government as a result of your negligence in the performance of any services furnished under the contract.

Although submissions required by your contract are technically reviewed by the Government, it is emphasized that your work must be prosecuted using proper internal controls and review procedures. The letter of transmittal for each submission which you make shall include a certification that the submission has been subjected to your own review and coordination procedures to insure (a) completeness for each discipline commensurate with the level of effort required for that submission, (b) elimination of conflicts, errors and omissions, and (c) the overall professional and technical accuracy of the submission. Documents which are significantly deficient in any of these areas will be returned to you for correction and/or upgrading prior to our completing our review. Contract submission dates will not be extended if a resubmission of draft material is required for this reason.

RIGHT-OF-ENTRY FOR SURVEY AND EXPLORATION

(Tract Number or Other Property Identification)

6. The land affected by this permit or right-of-entry is located in the State of Maine County of Aroostook, and is described as follows: As depicted on the Army Corps of Engineers map entitled "Ft. Fairfield Local Protection - Exploration Plan."

27th day of Jan. 1956
W. S. Andrews (SEAL)
For the Canadian Pacific Railway (SEAL)

By B. B. [Signature]

AMENDMENT TO RIGHT-OF-ENTRY

"Railway requires 48 hours' notice prior to commencement of any work to arrange flagging protection, if required and at no time should any equipment be placed closer than 10 feet to the nearest rail of any track."

whereas, hereinafter called the "Owner", hereby grants to the UNITED STATES OF AMERICA, hereinafter called the "Government", a permit or right-of-entry upon the following terms and conditions:

1. The Owner hereby grants to the Government an irrevocable right to enter upon the lands hereinafter described at any time within a period of six (6) months from the date of this instrument, in order to survey, make test borings, and carry out such other exploratory work as may be necessary to complete the investigation being made of said lands by the Government.
2. The permit includes the right of ingress and egress on other lands of the Owner not described below, provided such ingress and egress is necessary and not otherwise conveniently available to the Government.
3. All tools, equipment, and other property taken upon or placed upon the land by the Government shall remain the property of the Government and may be removed by the Government at any time within a reasonable period after the expiration of this permit or right-of-entry.
4. The Government agrees to be responsible for damages arising from the activity of the Government, its officers, employees, or representatives on said land, in the exercise of rights under this permit or right-of-entry, either by repairing such damage or at the option of the Government by making an appropriate settlement with the Owner in lieu thereof.
5. If aircraft flights over said lands, or entry upon the land by means of helicopter or other type aircraft, are necessary, the Government shall inform the Owner, in advance, of each such flight or entry.
6. The land affected by this permit or right-of-entry is located in the State of Maine County of Aroostook and is described as follows: As depicted on the Army Corps of Engineers map entitled "Fort Fairfield Local Protection-Exploration Plan." Land owned by Stephen F. & Elaine E. Novak, Assessor's Map #32, Lot #78. Test boring to be done in west driveway off Main Street, as shown on Corps of Engineers, Water Resources Investigation, St. John River Basin, Aroostook River, July 1983.
7. The test results will be given to the property owner, after drilling is completed.

WITNESS MY HAND AND SEAL this day of 19

Stephen F. Novak (SLA)

(SLA)

UNITED STATES OF AMERICA

By _____
RICHARD T. BOSACZYK
Chief, Real Estate Division

CEIVE

B-31
1145-TIME

Fort Fairfield Local Protection Project

Boring FD-11

Project, Description or Activity

Plot Number or Other Property Identification

I, the undersigned, hereinafter called the "Owner", hereby grants to the UNITED STATES OF AMERICA, hereinafter called the "Government", a permit or right-of-entry upon the following terms and conditions:

1. The Owner hereby grants to the Government an irrevocable right to enter upon the lands hereinafter described at any time within a period of six (6) months from the date of this instrument, in order to survey, make test borings, and carry out such other exploratory work as may be necessary to complete the investigation being made of said lands by the Government.

2. The permit includes the right of ingress and egress on other lands of the Owner not described below, provided such ingress and egress is necessary and not otherwise conveniently available to the Government.

3. All tools, equipment, and other property taken upon or placed upon the land by the Government shall remain the property of the Government and may be removed by the Government at any time within a reasonable period after the expiration of this permit or right-of-entry.

4. The Government agrees to be responsible for damages arising from the activity of the Government, its officers, employees, or representatives on said land, in the exercise of rights under this permit or right-of-entry, either by repairing such damage or at the option of the Government by making an appropriate settlement with the Owner in lieu thereof.

5. If aircraft flights over said lands, or entry upon the land by means of helicopter or other type aircraft, are necessary, the Government shall inform the Owner, in advance, of each such flight or entry.

6. The land affected by this permit or right-of-entry is located in the State of Maine, County of Aroostook, and is described as follows: As depicted on the Army Corps of Engineers map entitled "Fort Fairfield Local Protection - Exploration Plan."

Land owned by Gilbert Peterson, Family Trust, Assessor's Map#32, Lot #46. Test boring to be done as shown on Corps of Engineers, Water Resources Investigation, St. John River Basin, Aroostook River, July 1983.


WITNESS MY HAND AND SEAL this

2nd day of December 19 85
[Signature] - President (SEAL)
(SEAL)


UNITED STATES OF AMERICA

By


RICHARD T. BOGACZYK
Chief, Real Estate Division




PLAN
SCALE: 1"=80'



LOCATION MAP
SCALE IN MILES



PLAN
SCALE: 1"=80'





VICINITY MAP

LEGEND

- Exploration Location
FD-86-7
20'
Required Depth of Exploration
- Exploration Location (Previous Contract)
FD-1
Exploration Number
- Water Main / Sewer (at FD-86-12 also a telephone cable)
- Suspected Location of Piping
used to fill Oil Tanks from
Rail Cars on Siding

Note: Plan based on Field Survey by
U.S. Army Corps of Engineers,
June 1978



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASS.

WATER RESOURCES INVESTIGATION




ST. JOHN RIVER BASIN

AROOSTOOK RIVER

FORT FAIRFIELD LOCAL PROTECTION


SCALE AS SHOWN

JULY 1983



- LEGEND
- Exploration Location (Proposed)
 - Exploration Number
 - Required Depth of Exploration
 - Exploration Location (Previous Contract)
 - Exploration Number

Note: Plan based on Field Survey by
U.S. Army Corps of Engineers
June 1979



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASS.

WATER RESOURCES INVESTIGATION

ST. JOHN RIVER BASIN

AROOSTOOK RIVER

FORT FAIRFIELD LOCAL PROTECTION

EXPLORATION PLAN

SCALE AS SHOWN

JULY 1983

b. Project Site

The site is located adjacent to the Aroostook River along the Canadian Pacific Rail line in Fort Fairfield, ME.

c. Purpose

The subsurface investigations were to determine the foundation conditions adjacent to the Aroostook River for the proposed dike improvement project.

d. Authority

The Fort Fairfield Local Protection Project is funded under authority of Section 205 of the 1948 Flood Control act.

e. Scope of Investigation

Inspection and exploration instructions, which were provided by the Army Corps of Engineers, New England Division, are included in Section 3a. The subsurface investigation program employed drive sample borings with standard penetration tests.

Work under this delivery order consisted of locating seven (7) drive sample - SPT borings by means of taping the given distances as indicated on Attachment No. 2 of the delivery order (Section 3a). Elevations for the borings were roughly estimated from the contours shown on Attachment 2.

The drive sample - SPT borings were performed in accordance with paragraph 13, page C-21 of the specifications. Sampling intervals were 5 feet in the overburden or less where there was a significant change in the soil strata. The borings were advanced using a 3-1/4" I.D. hollow stem auger. All borings were terminated at the specified depth in overburden. The entire sample for each SPT drive was saved.


SECTION 4

QUALITY CONTROL

a. General Certification Statement

I hereby certify that the above mentioned records, equipment and procedures were used to perform the subsurface exploration described herein. I also certify that the work was performed in a professional manner and meets the requirements set forth in the delivery order. This report has been subject to my review and is both complete and technically accurate.

CERTIFIED 11 April 1986



Spencer F. Thew, P.E./L.S.

b. Records Taken

NED Forms 121, 58, 58a and 59 were used to record pertinent drilling and sampling operations including elevations, blow counts, etc. Section 8 contains a complete series of these logs for the seven borings along with location maps.

Summaries of daily activities and telephone logs can be found in Tables I and II of Section 5. A chain of custody log is in Section 6. The safety meeting report, NED Form 251, is located in Section 7.

c. Equipment Used

All equipment and supplies were provided by Atlantic Testing Laboratories, Limited. A listing of pertinent equipment follows:

- truck-mounted CME 55 drill rig
- 140 pound drive hammer used to advance the split spoon sampler
- 3-1/4" I.D. hollow stem augers
- 1-3/8" I.D. split spoon soil samplers, 2.0 ft in length
- AW-sized rods were used to advance the split spoon sampler.

d. Procedures

The boring locations were established by taping the distances given on Attachment No. 2 of the delivery order (Section 3a). The actual boring locations (Figure 3, Section 8c) varied from these specified locations due to site inaccessibility, difficulty in fine adjustments to the rig position due to the rails and/or the snow accumulation, or problems with utility clearance. Specific reasons for each location difference are noted on NED Form 58 under "General Remarks" for each boring in Section 8d. However, the following changes should be noted here:

1. FD-86-9(E) was moved from 15 ft to 37 ft from the centerline of the track due to water mains under the requested position. Town public utilities personnel requested that the boring be moved behind the pine tree on site.
2. FD-86-11(F) was moved 8.6 ft to the south in order to clear pipes used to empty tank cars on the siding into the oil tanks across the tracks to the north. It also should be noted that the soils at this site are strongly contaminated with spilled petroleum product.
3. FD-86-12(D) was moved from 20 ft to 26.2 ft from the wall of Peterson's Auto Parts due to water mains and a New England Telephone cable under the original site.
4. FD-86-13(C) was moved 6.5 ft to the south at the request of Mr. Novak in order to avoid crushing pine seedlings.

Elevations for the borings were roughly estimated from the contours on Attachment No. 2 of the delivery order (Section 3a).

The borings were advanced using a 3-1/4" I.D. hollow stem auger to 2.0 ft above the specified depth. The final two feet of the borings were completed by sampling.

Sampling was accomplished using a 1-3/8" I.D. split spoon sampler 2.0 ft in length. The sampler was advanced by a 140 pound hammer dropping in free fall from a height of 30 inches. Refusal was defined as 100 blows with a less than 12" penetration or bouncing refusal. The sample spoon shoes were kept reasonably sharp at all times. Dull, bent, or otherwise damaged samplers were not used.

The complete sample was saved and placed in 8 oz glass jars with hermetically sealed lids. The samples were not classified in the field due to one or more of the following reasons:

1. The samples were frozen.
2. The extreme cold of -10 to 10 degrees Fahrenheit threatened to freeze the samples.
3. It was snowing heavily.

The samples were brought to room temperature and classified in accordance with ASTM D-2488 no more than two days after sampling.

SECTION 5
SUMMARY OF ACTIVITIES
AND
TELEPHONE LOG

TABLE I

SUMMARY OF ACTIVITIES

<u>Date</u>	<u>Activity</u>
24 Feb	Monday: <ul style="list-style-type: none">- site inspector made arrangements to meet with Town and Railway officials 25 Feb 86.
25 Feb	Tuesday: on-site 12:00 - 17:30 <ul style="list-style-type: none">- site inspection made with Town and Railway officials.- utility clearance discussed.- boring locations were taped and staked.
26 Feb	Wednesday: <ul style="list-style-type: none">- site inspector discussed site conditions with Patrick Sullivan, Manager of the Canton Subsurface Exploration Division of Atlantic Testing Laboratories, Limited.
6 Mar	Thursday: <ul style="list-style-type: none">- geotechnical inspector mobilized to site.
7 Mar	Friday: on-site 08:00 - 16:00 <ul style="list-style-type: none">- obtain utility clearances for borings.- mobilize drilling equipment to site.
8 Mar	Saturday: on-site 08:30 - 10:30 <ul style="list-style-type: none">- site inspection with drillers.- secure planking necessary for on-site moves.
10 Mar	Monday: drillers on-site 07:00 - 17:30 <ul style="list-style-type: none">- complete utility clearance.- drill FD-86-7 (A) and FD-86-8 (B).- conduct safety meeting.- stand by time 4 hours for on-site moves, safety meeting and final utility clearance from New England Telephone.
11 Mar	Tuesday: drillers on-site 06:30 - 17:00 <ul style="list-style-type: none">- drill FD-86-9 (E), FD86-10 (G) and FD-86-11 (F). Note serious petroleum contamination of soils and water in FD-86-11.- notified Novak family of boring that will take place on their property tomorrow.- stand by time 3-1/2 hours for on-site moves.
12 Mar	Wednesday: drillers on-site 06:30 - 15:30 <ul style="list-style-type: none">- drill FD-86-12 (D) and FD-86-13 (C).- begin sample classification.- stand by time 6 hours for on-site moves and backfilling holes.
13 Mar	Thursday: <ul style="list-style-type: none">- complete sample classification.- travel to Portland, ME.

DateActivity

14 Mar

Friday: at NED complex 10:15 - 11:00
- travel to Waltham, MA.
- drop off samples with logs to Joseph Colucci of the
Materials Lab.
- visit Jim Blair, Terry Wong, John Hart.

TABLE II

TELEPHONE LOG

<u>Date</u>	<u>Conversation</u>
10 Mar	Monday: 08:05 and 08:30, Jim Blair <ul style="list-style-type: none">- continuous sampling? No - on 5 ft centers with final sample giving extra 2 ft of boring depth.- depth of Boring FD-A? 32 ft.- need jar labels. He will mail them to Sharon Flint.- need to move FD-E and FD-D because of utilities - will keep him appraised of situation.- Corps will provide mylar of plan of explorations.
11 Mar	Tuesday: 08:00, Jim Blair - not in <ul style="list-style-type: none">- left message re: job progress
12 Mar	Wednesday: 09:30, Paul L'Heureux <ul style="list-style-type: none">- job progress- expected completion schedule- need to classify soils sometime after they are taken- will bring samples to Waltham after classification.
14 Mar	Friday: 07:15, Jim Blair <ul style="list-style-type: none">- visit to Waltham - expect me in the morning <p>10:30 - 11:00, Jim Blair, Terry Wong, John Hart</p> <ul style="list-style-type: none">- charge an extra geotechnical day for sample classification.- put location of sewer lines, water mains, telephone cables on logs when the hole had to be moved because of them.- picked up mylar of Attachment No. 2.

SECTION 6

CHAIN OF CUSTODY LOG



atl

ATLANTIC TESTING LABORATORIES, Limited

CHAIN OF CUSTODY LOG

PROJECT:

Fort Fairfield ME
DACW 33-85-B-0011, D.O.#0009

ITEMS:

Tubes none

Bottles none

Jar Samples 100 Jars, 5 boxes FD-86-7 thru FD-86-13

Core Boxes none

Sampling Logs FD-86-7, 8, 9, 10, 11, 12, 13 (7)

<u>Date & Time Received</u>	<u>Date & Time Transferred</u>	<u>Comments</u>	<u>Custodian</u>
<u>0700, 10 March 86</u>		<u>as sampled</u>	<u>T Beddoe</u>
	<u>14 March 86, 10:30 AM</u>		<u>Joseph A. Gluski</u>

SECTION 7

SAFETY REPORTS

WEEKLY SAFETY MEETING

NEDSO

Date held 10 March 86THRU: Area Engineer, Fort Fairfield AreaTime 0930

TO: Safety Office, NED

1. Weekly safety meeting was held this date for the following personnel:

Contract No. D.O. #9 Contractor Atlantic Testing Labs, LtdConducted By TA Beddoe All personnel present (Contr) 3
(Sub) 1Subjects discussed (Note, delete, or add): (Govt)
EM 385-1-1, Section:

✓ Accident Prevention Plan

✓ Individual Protective Equipment - hard hats, gloves

✓ Prevention of Falls - esp. on slopes near river

✓ Back Injury, Safe Lifting Techniques - lifting of hammer.

✓ Fire Prevention - fire extinguisher in good condition.

✓ Sanitation, First Aid, Waste Disposal - check condition of First Aid Kit

✓ Tripping Hazards - trash, hose, nails in lumber - esp. rails and ties

Staging, Ladders, Concrete Forms, Safety Nets -

Hand Tools, Portable Power Tools, Woodworking Machinery -

✓ Equipment Inspection & Maintenance (Zero Defects) -

Hoisting Equipment -

✓ Ropes, Hooks, Chains and Slings -

Electrical Grounding, Temporary Wiring, GFCI -

Lockouts for safe clearance procedures - electrical, pressure, moving parts -

Welding, Cutting -

Excavations -

✓ Loose Rock and Steep Slopes - by river

Explosives -

Water Safety -

Toxic materials - hazards, MSDS, respiratory, ventilation -

Other - give emergency phone numbers, location of police, emergency services, hospital (in town)
Safety regarding chains Prepared by TA Beddoe Title

2. Forwarded.

Exposure hours 3/2/86 - 3/8/86

CF: ATL 12 man-hours

Total 12

Signature Theresa A. Beddoe
Resident Engineer

WEEKLY SAFETY MEETING

FOR THE CONSTRUCTION INDUSTRY

Safety Meeting Outlines

Week of

1986

Company Name Atlantic Testing Labs Job Name Fort Fairfield HE 0013 Date 10 March 86

LIFTING AND CARRYING

It's impossible to accomplish any job in the construction industry without lifting and carrying various tools, equipment, and materials, yet very few of you do it correctly.

Your back does a good job of holding you erect, but is sure has a lousy design when it comes to bending and lifting, and maybe that's why 75 million Americans suffer from back problems.

Improper lifting and carrying can also result in hernias, sprains, strains, fractured bones, and injuries from falls.

You'll be lifting and carrying the rest of your life -- make an effort now to break your bad habits, and DO IT RIGHT FROM NOW ON!

Rule number one -- THINK -- start every lift with your brain.

To lift, get a good footing, with feet about shoulder width apart.

Keep your back straight, and bend at the knees.

Lift with your legs while keeping your back straight.

NEVER twist your body while lifting.

NEVER reach and lift at the same time.

NEVER carry a package that blocks your vision.

Make sure that the floor is clear for good footing, and clean to avoid slipping.

Carry items close to your body to minimize back strain.

If the load is more than you can safely lift or carry -- GET HELP!

It's amazing how efficient and careful people can become at lifting and carrying AFTER they have injured their back. Doesn't it make good sense to lift and carry correctly to AVOID painful back problems? Remember to THINK, then do it right, starting today!

SAFETY REMINDERS

WHEN LIFTING MATERIALS WITH A CRANE, BE ALERT,
AND NEVER SWING THE LOAD OVER THE HEADS OF OTHERS.

Special Topics For Your Project watch overhead electrical lines; when drilling on
over side of tracks, be especially mindful of your footing; be
mindful of footing problems due to rails.

Employee Safety Recommendations

Meeting Attended By

TA Beddoe (ATL)

Kevin Hawkins (ATL)

Mark Hawkins (ATL)

Clayton Sullivan (CP Rail)

Supervisors Signature Theresa A. Beddoe

WEEKLY SAFETY MEETING

NEDSO

Date held _____

THRU: Area Engineer, Fort Fairfield Area

Time _____

TO: Safety Office, NED

1. Weekly safety meeting was held this date for the following personnel:

Contract No. D.O.#9 Contractor Atlantic Testing Labs, Ltd

Conducted By _____ All personnel present (Contr) _____
(Sub) _____

Subjects discussed (Note, delete, or add): (Govt) _____
EM 385-1-1, Section: _____

Accident Prevention Plan

Individual Protective Equipment -

Prevention of Falls -

Back Injury, Safe Lifting Techniques -

Fire Prevention -

Sanitation, First Aid, Waste Disposal -

Tripping Hazards - trash, hose, nails in lumber -

Staging, Ladders, Concrete Forms, Safety Nets -

Hand Tools, Portable Power Tools, Woodworking Machinery -

Equipment Inspection & Maintenance (Zero Defects) -

Hoisting Equipment -

Ropes, Hooks, Chains and Slings -

Electrical Grounding, Temporary Wiring, GFCI -

Lockouts for safe clearance procedures - electrical, pressure, moving parts -

Welding, Cutting -

Excavations -

Loose Rock and Steep Slopes -

Explosives -

Water Safety -

Toxic materials - hazards, MSDS, respiratory, ventilation -

Other - Exposure hours 3/9/86-3/15/86

ATL 86.5

Prepared by YMB Title _____

2. Forwarded. CP Rail 10

CF:

96.50

Signature Theresa A. Beddoe
Resident Engineer

Note: No work done on site

3/9 Sunday, 3/13/86 Thursday - 3/15/86 Saturday

NED ^{FL} _{APR 25} 251

Time for geotechnical inspector's soil classification
10.25 hours on 3/12/86 Wednesday - 3/13/86 Thur

SECTION 8

BORING LOGS

a. Figure 1 - General Project Map


GENERAL PROJECT MAP



b. Figure 2 – Site Location Map

FIGURE 2

SITE LOCATION MAP



PROJECT No CD013

SCALE: 1:62,500

U.S.G.S. QUAD: Fort Fairfield, ME

c. Figure 3 - Boring Location Plan

ALIGNMENTS
NO. 1 AND NO. 2PLAN
SCALE: 1"=80'ALIGNMENTS
NO. 1 AND NO. 2PLAN
SCALE: 1"=80'

LEGEND


FD-C
20'
Exploration Location (Proposed)
Exploration Number
Required Depth of Exploration

FD-1
Exploration Location (Previous Contract)
Exploration Number

Note: Plan based on Field Survey by
US Army Corps of Engineers
June 1975

GRAPHIC SCALES

1"=80' 0' 80' 160'
1"=10' 0' 10' 20'

LOCATION MAP
SCALE: 1"=100'

VICINITY MAP

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASS.

WATER RESOURCES INVESTIGATION

ST. JOHN RIVER BASIN

AROOSTOOK RIVER

FORT FAIRFIELD LOCAL PROTECTION

EXPLORATION PLAN
SCALE AS SHOWN

JULY 1983

d. Boring Logs

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Fort Fairfield, ME. PROJECT NO. D.O. # 9
Page 1 of 5 Pages
Hole No. FO-86-7 Diam. (Casing) 3 1/4" Hollow Stem Auger Boring Started 10 March 86
Co-ordinates: N X see boring location plan Boring Completed 10 March 86
Drilled by Mark + Kevin Hawkins Report Submitted 18 March 86

Purpose of Exploration determine foundation conditions for dike improvement project

Elevation Top of Hole 361 ± * M.S.L. Casing Left in Place Feet
Total Overburden Drilled 32 Feet
Elevation Top of Rock M.S.L.
Elevation Bottom of Hole 329 ± * M.S.L.
Total Rock Drilled Feet
Total Depth of Hole 32 Feet
Core Recovered %
Core Recovered Ft.; Diam. In.
Soil Samples 1 3/8 In. Diam. 7 No.
Soil Samples In. Diam. No.
Water Table Depth 12.3'

* Elevations interpolated from Attachment 2 of D.O.

Depth		Method of Drilling and Type of Bit Used	INDEX	
From	To			
0	30	3 1/4" I.D. Hollow Stem Auger	Ground Water	Back of Page <u>5</u>
30	32	1 3/8" I.D. SPT Sampler	Boring Location Sketch	Back of Page <u>5</u>
			Overburden Record	Page <u>2-4</u>
			Rock Drilling	Page <u> </u>
				Page <u> </u>
				Page <u> </u>
				Page <u> </u>

Prepared by TA Beddoe

Field Data

Lab. Data

Submitted by Atlantic Testing Labs, Ltd.

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Fort Fairfield, ME. Page 2 of 5 Pages

Boring No. 7 Desig. A Diam. (Casing) 3 1/4"

FIELD LOG OF TEST BORING

Co-ordinates: X see Boring & Location Plan

Elevation Top of Boring 361 ± * M.S.L. Hammer Wt. 140 # Boring Started 10 Mar 86
Total Overburden Drilled 32 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left — Boring Completed 10 Mar 86
Total Rock Drilled — Feet (Subsurface Water Data) — (Page 5)
Elevation Bottom of Boring 329 ± * M.S.L. Obs. Well no
Total Depth of Boring 32 Feet Drilled By Mark + Kevin Hawkins
Core Recovered — % No. Boxes — Mfg. Drs. Drill Huck mounted CME 55
Core Recovered — Ft : — Diam. — In. Inspected By: TA Beddoe
Soil Samples 1 3/8 In. Diam. 7 No. Classification By: TA Beddoe
Soil Samples — In. Diam. — No. Classification By: —

DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECVY	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0'	1" = 2'	NO.	SIZE			
2.0'		S-1	1 3/8	95% 24 44 58 77	3 1/4" Hollow Stem Auger Sampling by 1 3/8" I.D. by 2' long split spoon soil sampler Augering easy for full depth of boring	Brown cmp SAND and GRAVEL, little SILT (moist, nonplastic) Note greater amount of SILT with depth. Dense because of frost. SW FILL
5.0'		S-2	1 3/8	75% 79 57 73 77		Brown cmp SAND and GRAVEL, trace SILT (dry, nonplastic) dense SW
7.0'						
10.0'						9.0' Note change to greater amount of SAND.

GENERAL REMARKS:

Boring only 5.3' from d of track due to
inaccessibility of further distances and due to
probability of intercepting concrete wall.

*Elevations interpolated from Attachment #2 of D.O.

Site

Fort Fairfield, ME.

Boring No.

FD-86-7

Page 3

of 5

DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECVY	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
10.0'	1.0'	NO.	SIZE			
12.0'		S-3	1 3/8	85% REC	7/12 13/21	Brown cmf SAND, some cf GRAVEL, trace SILT (dry, non plastic) slightly dense SW
15.0'					Augering easy for full depth of boring water table measured at 12.3'	Similar soils, wet
17.0'		S-4	1 3/8	80% 7/24 37/52		Brown cf GRAVEL, little cmf SAND, trace SILT (saturated, non plastic) Slightly Dense GW
20.0'						Brown cmf SAND, little cf GRAVEL, trace SILT (saturated, non plastic) slightly dense SW
22.0'		S-5	1 3/8	70% 12/23 23/20		Brown cf GRAVEL, little cmf SAND, trace SILT (saturated, non plas- tic) slightly dense GW
25.0'						
27.0'		S-6	1 3/8	60% 13/17 17/10		Brown cmf SAND and cf GRAVEL, little SILT (sat- urated, non plastic) slightly dense SW

Site Fort Fairfield, ME.				Boring No. FD-86-7		Page 4 of 5	
DEPTH		CORE/SAMPLE		BLOWS PER FT.	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS	
27.0'	1'-2'	NO.	SIZE	RECY COR RECY			
27.0'	1'-2'			REC	3 1/4" Hollow Stem Auger sampling by 1 3/8" I.D. by 2' long split spoon soil sampler augering easy for full depth of boring		
30.0'					end of augering		
32.0'		5-7	1 3/8	65%	10 16 29 27	Brown of GRAVEL and cmf SAND, little SILT (satura- ted, nonplastic) slightly dense GW	
					Bottom of hole at 32.0' as instructed in D.O.		

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Fort Fairfield, ME. PROJECT NO. D.O. # 9
Page 1 of 5 Pages
Hole No. FD-86-2 Diam. (Casing) 3 1/4" Hollow Stem Auger Boring Started 10 March 86
Co-ordinates: see boring location sketch Boring Completed 10 March 86
Drilled by Mark & Kevin Hawkins Report Submitted 18 March 86
Purpose of Exploration determine foundation conditions for dike improvement project

Elevation Top of Hole 361 ± * M.S.L. Casing Left in Place _____ Feet
Total Overburden Drilled 32 Feet
Elevation Top of Rock _____ M.S.L.
Elevation Bottom of Hole 329 ± * M.S.L.
Total Rock Drilled _____ Feet
Total Depth of Hole 32 Feet
Core Recovered _____ %
Core Recovered _____ Ft.; _____ Diam. _____ In.
Soil Samples 1 3/8 In. Diam. 7 No.
Soil Samples _____ In. Diam. _____ No.
* Elevations interpolated from Attachment 2 of D.O.
Water Table Depth 13.8'

Depth		Method of Drilling and Type of Bit Used	INDEX	
From	To			
0	30	3 1/4" I.D. Hollow Stem Auger	Ground Water	Back of Page <u>5</u>
30	32	1 3/8" I.D. SPT Sampler	Boring Location Sketch	Back of Page <u>5</u>
			Overburden Record	Page <u>2-4</u>
			Rock Drilling	Page _____
				Page _____
				Page _____
				Page _____

Prepared by T A Beddoe Field Data
Submitted by Atlantic Testing Labs, Ltd. Lab. Data

U. S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION				Site <u>Fort Fairfield, ME.</u> Page <u>2</u> of <u>5</u> Pages			
				Boring No. <u>FD-86-8</u> Desig. <u>B</u> Diam. (Casing) <u>3 1/4"</u>			
FIELD LOG OF TEST BORING				Co-ordinates: <u>See Boring</u> & <u>Location Sketch</u>			

Elevation Top of Boring <u>361 ± *</u>	M.S.L.	Hammer Wt. <u>140#</u>	Boring Started <u>10 Mar 86</u>
Total Overburden Drilled <u>32</u>	Feet	Hammer Drop <u>30"</u>	Boring Completed <u>10 Mar 86</u>
Elevation Top of Rock <u>—</u>	M.S.L.	Casing Left <u>none</u>	
Total Rock Drilled <u>—</u>	Feet	Subsurface Water Data <u>—</u>	Page <u>5</u>
Elevation Bottom of Boring <u>329 ± *</u>	M.S.L.	Obs. Well <u>no</u>	
Total Depth of Boring <u>32</u>	Feet	Drilled By <u>Mark + Kevin Hawkins</u>	
Core Recovered <u>—</u> %	No. Boxes <u>—</u>	Mfg. Dr. Drill <u>truck mounted CME 55</u>	
Core Recovered <u>—</u> Ft	Diam. <u>—</u> In.	Inspected By <u>TA Beddoe</u>	
Soil Samples <u>1 3/8</u>	In. Diam. <u>7</u> No.	Classification By <u>TA Beddoe</u>	
Soil Samples <u>—</u>	In. Diam. <u>—</u> No.	Classification By <u>—</u>	

DEPTH		CORE/SAMPLE		BLOWS PER FT.	4" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
D'	1" = 2'	NO.	SIZE	DEPTH SAMPLER CORRECTION		
2.0'		S-1	1 3/8	60%	3 1/4" Hollow Stem Auger Sampling by 1 3/8" I.D. by 2' long split spoon soil sampler Augering easy for full depth of boring	Brown SILT, little m ^p SAND, little ORGANIC MATTER, trace of GRAVEL, trace CLAY (wet, slightly plastic) loose MH
5.0'		S-2	1 3/8	50%		Brown SILT, some GRAVEL, little CLAY, little m ^p SAND, trace ORGANIC MATTER (wet, plastic) loose MH
10.0'						

GENERAL REMARKS: Boring only 6.3' from center-line of tracks because of inaccessibility of further distances due to precipitous drop off to river.
 *Elevations interpolated from Attachment 2 of D.O.

Site Fort Fairfield, ME.				Boring No. FD-86-8		Page <u>3</u> of <u>5</u>	
DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECORDED	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS	
10.0'	1' 2'	NO.	SIZE				
12.0'		5-3	1 3/8	REC 90%	3/4" Hollow Stem Auger Sampling by 1 3/8" I.D. by 2' long split spoon soil sampler. Augering easy for full depth of boring. Water Table measured at 13.8'	Brown fine SAND, some SILT, trace CLAY (wet, slightly plastic) loose SP	
15.0'						Brown SILT, some fine SAND, trace CLAY (saturated, slightly plastic) loose ML	
17.0'		5-4	1 3/8	90%		Brown mf SAND, some SILT (saturated, nonplastic) loose ML interlayered with varved black + brown SILT, trace fine SAND, trace CLAY (sat- urated, very slightly plastic) loose ML	
20.0'							
22.0'		5-5	1 3/8	100%		Dark Brown cmf SAND, little SILT (saturated, nonplastic) loose SW	
25.0'							
27.0'		5-6	1 3/8	100%		Similar Soils	
						Brown cmf SAND and CF GRAVEL, some SILT (wet,	

Site Fort Fairfield, ME.	Boring No. FD-86-8	Page <u>4</u> of <u>5</u>
-----------------------------	-----------------------	------------------------------

DEPTH	CORE/SAMPLE		BLOWS PER FT	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO.	SIZE	DEPTH FEET		
27.0'	1-2'				
			REC	3/4" Hollow stem Auger sampling by 1 3/8" I.D. by 2' long split spoon soil sampler Augering easy for full depth of boring.	non-plastic) slightly dense SW
30.0'				end of augering	
	5-7	1 3/8	100%	15 34' 33 37	Brown cmf SAND, some SILT (wet, non plastic) slightly dense SW Brown cf GRAVEL, some cmf SAND, little SILT (wet, non- plastic) dense GW
32.0'				Bottom of hole at 32.0' as instructed in D.O.	

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Fort Fairfield, ME. PROJECT NO. D.O. # 9
Page 1 of 5 Pages

Hole No. ED-86-9 Diam. (Casing) 3 1/4" Hollow Stem Auger Boring Started 11 March 86

Co-ordinates: N 6 E & boring location sketch

Boring Completed 11 March 86

Drilled by Mark & Kevin Hawkins

Report Submitted 18 March 86

Purpose of Exploration determine foundation conditions for dike improvement project

Elevation Top of Hole 363 ± * M.S.L.

Casing Left in Place _____ Feet

Total Overburden Drilled 32 Feet

Elevation Top of Rock _____ M.S.L.

Elevation Bottom of Hole 331 ± * M.S.L.

Total Rock Drilled _____ Feet

Total Depth of Hole 32 Feet

* Elevations interpolated from Attachment 2 of D.O.

Core Recovered _____ %

Core Recovered _____ Ft.; _____ Diam. _____ In.

Soil Samples 1 3/8 In. Diam. 7 No.

Soil Samples _____ In. Diam. _____ No.

Water Table Depth 13.5'

Depth		Method of Drilling and Type of Bit Used
From	To	
0	30	3 1/4" I.D. Hollow Stem Auger
30	32	1 3/8" I.D. SPT Sampler

INDEX	
Ground Water _____	Back of Page <u>5</u>
Boring Location Sketch _____	Back of Page <u>5</u>
Overburden Record _____	Page <u>2-1</u>
Rock Drilling _____	Page _____
_____	Page _____
_____	Page _____
_____	Page _____

Prepared by T A Beddoe Field Data

Lab. Data

Submitted by Atlantic Testing Labs, Ltd

U. S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		Site <u>Fort Fairfield, ME.</u> Page 2 of 5 Pages Boring No. <u>9</u> Desig. <u>E</u> Diam. (Casing) <u>3 1/4"</u> Co-ordinates: <u>N sec Boring</u> <u>E Location Plan</u>	
FIELD LOG OF TEST BORING			
Elevation Top of Boring <u>343 ± *</u> M.S.L.		Hammer Wt. <u>140 #</u> Boring Started <u>11 Mar 86</u>	
Total Overburden Drilled <u>32</u> Feet		Hammer Drop <u>30"</u>	
Elevation Top of Rock <u>—</u> M.S.L.		Casing Left <u>—</u> Boring Completed <u>11 Mar 86</u>	
Total Rock Drilled <u>—</u> Feet		Subsurface Water Data <u>—</u> Page <u>5</u>	
Elevation Bottom of Boring <u>331 ± *</u> M.S.L.		Obs. Well <u>ND</u>	
Total Depth of Boring <u>32'</u> Feet		Drilled By <u>Mark + Kevin Hawkins</u>	
Core Recovered <u>—</u> % No. Boxes <u>—</u>		Mfg. Des. Drill <u>truck mounted CMESS</u>	
Core Recovered <u>—</u> Ft : <u>—</u> Diam. <u>—</u> In.		Inspected By <u>TA Beddor</u>	
Soil Samples <u>1 3/8</u> In. Diam. <u>7</u> No.		Classification By <u>TA Beddor</u>	
Soil Samples <u>—</u> In. Diam. <u>—</u> No.		Classification By <u>—</u>	

DEPTH		CORE/SAMPLE		BLOWS PER FOOT CORE RECOVERED	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0'	1' - 2'	NO.	SIZE			
0'	1.5'	S-1	1 3/8	70%	3 1/4" Hollow Stem Auger Sampling by 1 3/8" I.O. by 2' long split spoon soil sampler. Augering easy for full depth of boring	Brown SILT, some MP SAND, little of GRAVEL, little CLAY, trace ORGANIC MATTER (grass, roots) (moist, slightly plastic) dense because of frost MH FILL
5.0'	7.0'	S-2	1 3/8	25%		Dark brown SILT, some CLAY, little fine SAND, trace of GRAVEL, trace ORGANIC MATTER (roots) (moist, plastic) slight odor of petroleum product, loose, MH FILL
10.0'						

GENERAL REMARKS:
 Boring moved due to water main under
 requested location.
 *Elevations interpolated from Attachment #2 of
 D.O.

Site Fort Fairfield, ME.				Boring No. FD-86-9		Page <u>3</u> of <u>5</u>	
DEPTH		CORE/SAMPLE		BLOWS PER FT	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS	
10.0'	1" 2'	NO.	SIZE	DEPTH RANGE RECOVER			
10.0'		S-3	1 3/8	50%	1 1 2 4	3 1/4" Hollow Stem Auger Sampling by 1 3/8" I.D. by 2' long split spoon soil sampler Augering easy for full depth of boring. S-3's poor recovery due to plugging of spoon with large gravel. - Water Table measured at 13.5'	Brown SILT and CLAY, little fine SAND, trace of GRAVEL (wet, plastic) loose MH
15.0'		S-4	1 3/8	50%	16 20 21 22		
17.0'							Brown of GRAVEL and fine SAND, some SILT with layers of Brown SILT and CLAY, trace fine SAND (wet, nonplastic) slightly dense GW
20.0'							
22.0'		S-5	1 3/8	70%	8 10 14 14		Brown of GRAVEL and fine SAND, some SILT (saturated, nonplastic) slightly dense GW
25.0'							
27.0'		S-6	1 3/8	60%	9 20 21 19		Similar soils GW

Site Fort Fairfield, ME.				Boring No. FD-86-9		Page <u>4</u> of <u>5</u>	
DEPTH	CORE/SAMPLE		BLOWS PER FT.	6" SAMPLING AND CORING OPERATIONS		CLASSIFICATION OF MATERIALS	
27.0'	1" 2'	NO.	SIZE	DEPTH RANGE	CORE RECY		
				REC		3/4" Hollow Stem Auger sampling by 1 3/8" I.D. by 2' long split spoon soil sampler. Augering easy for full depth of boring.	
30.0'						end of augering	
		5-7	1 3/8	50%	18 22 17 26	Similar Soils GW	
32.0'						Brown SILT and CLAY, some ME SAND, trace fine GRAVEL (moist, plastic) slightly dense MH TILL	
						Bottom of hole at 32.0' as instructed in D.O.	

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Fort Fairfield, ME. PROJECT NO. D.O. #9
Page 1 of 4 Pages
Hole No. FD-86-10 Diam. (Casing) 3 1/4" Hollow Stem Auger Boring Started 11 March 86
Co-ordinates: see boring location sketch Boring Completed 11 March 86
Drilled by Mark & Kevin Hawkins Report Submitted 18 March 86

Purpose of Exploration determine foundation conditions for dike improvement project

Elevation Top of Hole 361 ± * M.S.L. Casing Left in Place — Feet
Total Overburden Drilled 22 Feet
Elevation Top of Rock — M.S.L.
Elevation Bottom of Hole 339 ± * M.S.L.
Total Rock Drilled — Feet
Total Depth of Hole 22 Feet
Core Recovered — %
Core Recovered — Ft.; — Diam. — In.
Soil Samples 1 3/8 In. Diam. 5 No.
Soil Samples — In. Diam. — No.
Water Table Depth 12.8'

* Elevations interpolated from Attachment 2 of D.O.

Depth		Method of Drilling and Type of Bit Used	INDEX	
From	To			
0	20	3 1/4" ID Hollow Stem Auger	Ground Water	Back of Page <u>4</u>
20	22	1 3/8" ID SPT Sampler	Boring Location Sketch	Back of Page <u>4</u>
			Overburden Record	Page <u>2+3</u>
			Rock Drilling	Page <u>—</u>
				Page <u>—</u>
				Page <u>—</u>
				Page <u>—</u>

Prepared by TA Beddoe
Field Data
Submitted by Atlantic Testing Labs, Ltd.

Lab. Data

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Fort Fairfield, ME. Page 2 of 4 Pages

FD-26-

Boring No. 10 Desig. G Diam. (Casing) 3 1/4"

FIELD LOG OF TEST BORING

Co-ordinates: N see Boring X Location Sketch

Elevation Top of Boring 361 ± * M.S.L. Hammer Wt. 140# Boring Started 11 Mar 86
Total Overburden Drilled 22 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left — Boring Completed 11 Mar 86
Total Rock Drilled — Feet | Subsurface Water Data | Page 4
Elevation Bottom of Boring 339 ± * M.S.L. | Obs. Well NO
Total Depth of Boring 22 Feet | Drilled By Mark + Kevin Hawkins
Core Recovered — % No. Boxes — Mfg. Des. Drill truck mounted CME 55
Core Recovered — Ft. — Diam. — In. Inspected By: TA Beddoe
Soil Samples 1 3/8 In. Diam. 5 No. Classification By: TA Beddoe
Soil Samples — In. Diam. — No. Classification By: —

DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECOVERED	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0'	1" 2'	NO.	SIZE			
0.0'				REC	3 1/4" Hollow Stem Auger Sampling by 1 3/8" I.D. by 2' long split spoon soil sampler Augering easy for full depth of boring	Black SILT and cmf SAND, little & GRAVEL, trace ORGANIC MATTER (wet, nonplastic) dense due to frost, ML FILL
		S-1	1 3/8	80%		
				25 50 44 42		
2.0'						
						Brown mf SAND, little & GRAVEL, trace SILT (moist, nonplastic) slightly dense SP
		S-2	1 3/8	80%		
				9 16 14 17		
5.0'						
7.0'						
10.0'						

GENERAL REMARKS:

Elevations interpolated from Attachment 2 of
D.O.
Boring moved due to difficulty of line
adjustments to rig position because of
rails and snow.

Site Fort Fairfield, ME.					Boring No. FD-86-10		Page <u>5</u> of <u>4</u>	
DEPTH		CORE/SAMPLE		BLOWS PER FOOT	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS		
10.0'	1" 2'	NO.	SIZE	DEPT CORRECTION				
10.0'				12.0'				
		S-3	1 3/8	35%	3 1/4" Hollow Stem Auger sampling by 1 3/8" I.D. by 2' long split spoon soil sampler Augering easy for full depth of boring - Water Table measured at 12.8'	Brown m st SAND, some of GRAVEL, little SILT (wet, nonplastic) slightly dense SD		
12.0'								
15.0'								
		S-4	1 3/8	75%	20 30 28 37	Brown of GRAVEL, some cm st SAND, little SILT (wet, nonplastic) fairly dense GW		
17.0'								
20.0'								
					end of augering			
22.0'								
		S-5	1 3/8	85%	13 29 32 35	Brown cm st SAND, some SILT, little of GRAVEL, with some pure inorganic SILT layers (saturated, nonplastic) fairly dense SW		
22.0'								
					Bottom of hole at 22.0' as instructed in D.O.			


Boring No: FD-86-10

Page 4 of 4

SUBSURFACE WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below original ground



CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Fort Fairfield, ME. PROJECT NO. D.O. #9
 Page 1 of 5 Pages
 Hole No. FD-86-11 Diam. (Casing) 3 1/4" Hollow Stem Auger Boring Started 11 March 86
 Co-ordinates: N see boring location sketch Boring Completed 11 March 86
 Drilled by Mark + Kevin Hawkins Report Submitted 12 March 86
 Purpose of Exploration determine foundation conditions for dike improvement project

Elevation Top of Hole 360 ± * M.S.L. Casing Left in Place _____ Feet
 Total Overburden Drilled 32 Feet
 Elevation Top of Rock _____ M.S.L.
 Elevation Bottom of Hole 328 ± * M.S.L.
 Total Rock Drilled _____ Feet
 Total Depth of Hole 32 Feet
 Core Recovered _____ %
 Core Recovered _____ Ft.; _____ Diam. _____ In.
 Soil Samples 13/8 In. Diam. 7 No.
 Soil Samples _____ In. Diam. _____ No.
 Water Table Depth 17.1'

* Elevations interpolated from Attachment 2 of D.O.

Depth		Method of Drilling and Type of Bit Used	INDEX
From	To		
0	30	3 1/4" I.D. Hollow Stem Auger	Ground Water _____ Back of Page <u>5</u>
30	32	1 3/8" I.D. SPT Sampler	Boring Location Sketch _____ Back of Page <u>5</u>
			Overburden Record _____ Page <u>2-4</u>
			Rock Drilling _____ Page _____
			_____ Page _____
			_____ Page _____
			_____ Page _____

Prepared by T A Beddoe Field Data
 Submitted by Atlantic Testing Labs, Ltd. Lab. Data

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Fort Fairfield, ME. Page 2 of 5 Pages

Boring No. FD-86-11 Desig. F Diam. (Casing) 3 1/4"

FIELD LOG OF TEST BORING

Co-ordinates: N sec Boring E Location Plan

Elevation Top of Boring 340 ± * M.S.L. Hammer Wt. 140 # Boring Started 11 Mar 86
Total Overburden Drilled 32 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left — Boring Completed 11 Mar 86
Total Rock Drilled — Feet (Subsurface Water Data) — (Page 5)
Elevation Bottom of Boring 328 ± * M.S.L. Obs. Well NO
Total Depth of Boring 32 Feet Drilled By Mark + Kevin Hawkins
Core Recovered — % No. Boxes — Mfg. Drs. Drill truck mounted CMES
Core Recovered — Ft. — Diam. — In. Inspected By: TA Beddoe
Soil Samples 1 3/8 In. Diam. 7 No. Classification By: TA Beddoe
Soil Samples — In. Diam. — No. Classification By: —

DEPTH D'	Ft. & In.	CORE/SAMPLE		BLOWS PER FT. CORE RECOVERY	L" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
		NO.	SIZE			
0.0'		S-1	1 3/8	REC 31/106 BSZ	3 1/4" I.D. Hollow Stem Auger Sampling by 1 3/8" I.D. by 2' long split spoon soil sampler Augering easy for full depth of boring S-1 refusal due to frost	Black fine GRAVEL and cmf SAND, some SILT (wet, nonplastic) dense due to frost GP FILL (based on appearance, texture and odor)
5.0'						
7.0'		S-2	1 3/8	5% 4/4 4/4	Grab sample from auger at ~6.0'	Black cmf SAND and light brown SILT, trace of GRAVEL (saturated, non- plastic) loose ML - slight petroleum product odor Auger sample - similar soils ML (moist)
10.0'						

GENERAL REMARKS:

*Elevations interpolated from Attachment 2 of D.O.
Boring moved to avoid pipes used to
unload tank cars.
**Contamination due to spills from unloading
rail cars by the siding.

Site Fort Fairfield, ME.				Boring No. FD-86-11		Page <u>3</u> of <u>5</u>		
DEPTH		CORE/SAMPLE		BLOWS PER FT.	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS		
10.0'	1' 2'	NO.	SIZE	DEPTH CORRECTION				
12.0'		S-3	1 3/8	75%	11 13 14 18	3 1/4" I.D. Hollow Stem Auger Sampling by 1 3/8" I.D. by 2' long split spoon soil sampler Augering easy for full depth of boring		Grey cmf SAND, some cf GRAVEL, little SILT (moist, nonplastic) slightly dense sw, strong petroleum odor
15.0'								
15.5'		S-4	1 3/8	40%	100 Bounce	Bouncing Refusal		Grey cmf SAND and cf GRAVEL, little SILT (wet, non- plastic) dense sw, strong petroleum odor, spoon dripped petroleum sheen when pulled. ** (see general remarks).
20.0'								
26.0'		S-5	1 3/8	45%	3 4 7 12			Grey f. SAND, little SILT, trace coarse GRAVEL (wet, nonplastic) loose SP, petroleum odor
25.0'								
27.0'		S-6	1 3/8	100%	4 7 9 12			Black mf SAND, trace SILT with two 1/2" layers of brown SILT at 26.0' and 27.0' (wet, nonplastic) loose SP, petro- leum odor

- Water Table measured
at 17.1'

DEPTH		CORE/SAMPLE		BLOWS PER FT	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
1" 2'	NO.	SIZE	DEPTH RANGE	CORRECTION		
27.0'				12EC	3 1/4" I.D. Hollow Stem Auger Sampling by 1 3/8" I.D. by 2' long split spoon soil sampler Augering easy for full depth of boring	
30.0'					end of augering	
32.0'		S-7	1 3/8"	70%	15 7 1/2 11 12	Grey SILT, trace cmf SAND at 30.0' (wet, nonplastic) loose ML
					Bottom of hole at 32.0' as instructed in D.O.	

Boring No: FD-86-11

Page 5 of 5


SUBSURFACE WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below original ground

BORING LOCATION SKETCH

Not to Scale



CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Fort Fairfield, ME. PROJECT NO. D.O.#9 Page 1 of 4 Pages
Hole No. 12 ^{FD-86-} Diam. (Casing) 3 1/4" Hollow Stem Auger Boring Started 12 March 86
Co-ordinates: X see boring location sketch Boring Completed 12 March 86
Drilled by Mark + Kevin Hawkins Report Submitted 18 March 86

Purpose of Exploration determine foundation conditions for dike improvement project

Elevation Top of Hole 368 * M.S.L. Casing Left in Place _____ Feet
Total Overburden Drilled 12 Feet
Elevation Top of Rock _____ M.S.L.
Elevation Bottom of Hole 356 * M.S.L.
Total Rock Drilled _____ Feet
Total Depth of Hole 12 Feet
Core Recovered _____ %
Core Recovered _____ Ft.: _____ Diam. _____ In.
Soil Samples 1 3/8 In. Diam. 3 No.
Soil Samples _____ In. Diam. _____ No.
* Elevations provided by reviewer of draft report.
Water Table Depth dry

Depth		Method of Drilling and Type of Bit Used	INDEX	
From	To			
0	10	3 1/4" I.D. Hollow Stem Auger	Ground Water	Back of Page <u>4</u>
10	12	1 3/8" I.D. SPT Sampler	Boring Location Sketch	Back of Page <u>4</u>
			Overburden Record	Page <u>2-3</u>
			Rock Drilling	Page _____
				Page _____
				Page _____
				Page _____

Prepared by T.A. Beddoe Field Data
Submitted by Atlantic Testing Labs, Ltd. Lab. Data

U. S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		Site <u>Fort Fairfield, ME.</u> Page 2 of <u>4</u> Pages Boring No. <u>12</u> Desig. <u>D</u> Diam. (Casing) <u>3 1/4"</u> Co-ordinates: <u>N see Boring</u> & <u>Location Sketch</u>	
FIELD LOG OF TEST BORING			
Elevation Top of Boring <u>368*</u> M.S.L.		Hammer Wt. <u>140#</u>	Boring Started <u>12 Mar 86</u>
Total Overburden Drilled <u>12</u> Feet		Hammer Drop <u>30"</u>	Boring Completed <u>12 Mar 86</u>
Elevation Top of Rock <u>—</u> M.S.L.		Casing Left <u>—</u>	
Total Rock Drilled <u>—</u> Feet		Subsurface Water Data <u>—</u>	Page <u>4</u>
Elevation Bottom of Boring <u>356*</u> M.S.L.		Obs. Well <u>no</u>	
Total Depth of Boring <u>12</u> Feet		Drilled By <u>Mark + Kevin Hawkins</u>	
Core Recovered <u>—</u> % No. Boxes <u>—</u>		Mfg. Dr. Drill <u>truck mounted CHE 55</u>	
Core Recovered <u>—</u> Ft : <u>—</u> Diam. <u>—</u> In.		Inspected By: <u>TA Beddoe</u>	
Soil Samples <u>13/8</u> In. Diam. <u>3</u> No.		Classification By: <u>TA Beddoe</u>	
Soil Samples <u>—</u> In. Diam. <u>—</u> No.		Classification By: <u>—</u>	

DEPTH		CORE/SAMPLE		BLOWS PER FT.	4" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0'	1" 2'	NO.	SIZE	PERCENT CORE RECOVERY		
0.25'				12/100	3 1/4" I.D. Hollow Stem Auger Sampling by 1 3/8" I.D. by 2' long split spoon soil sampler S-1 encountered bouncing refusal	3" asphalt Brown cnp SAND and SILT, some fine GRAVEL, (wet, nonplastic) dense SW
2.25'		S-1	1 3/8	100%		Augering difficult from 2'-4' because of boulders
4.5'					Augering easy for remainder of boring.	change at 4.0'
6.5'		S-2	1 3/8	80%		Brown SILT, little P. SAND, (moist, non plastic) loose ML
10.0'						end of augering

GENERAL REMARKS:
 * Elevations provided by reviewer of draft report.
 Boring moved due to water main and New England Telephone Cable under original location.

Site				Boring No.		Page	
Font Fairfield, ME.				FD-86-12		3 of 4	
DEPTH		CORE/SAMPLE		BLOWS PER FT.		6" SAMPLING AND CORING OPERATIONS	
10.0'	11.0'	NO.	SIZE	DEPTH FOOT	RECVY	CLASSIFICATION OF MATERIALS	
10.0'	11.0'	S-3	1 3/8"	65%	5 4 4 3	3/4" I.D. Hollow Stem Auger Sampling by 1 3/8" I.D. by 2' long split spoon soil sampler Brown m st SAND and SILT, little of GRAVEL (moist, nonplastic) loose SP	
12.0'						Bottom of hole at 12.0' as instructed in D.O.	

Boring No: FD-86-12

Page 4 of 4


SUBSURFACE WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below original ground

BORING LOCATION SKETCH

Not to scale



CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Fort Fairfield, ME. PROJECT NO. D.O. #9
Page 1 of 4 Pages
Hole No. FD-86-13 Diam. (Casing) 3/4" Hollow Stem Auger Boring Started 18 March 86
Co-ordinates: see boring location sketch Boring Completed 18 March 86
Drilled by Mark + Kevin Hawkins Report Submitted 18 March 86

Purpose of Exploration determine foundation conditions for dike improvement project

Elevation Top of Hole 379 * M.S.L. Casing Left in Place — Feet
Total Overburden Drilled 17 Feet
Elevation Top of Rock — M.S.L.
Elevation Bottom of Hole 362 * M.S.L.
Total Rock Drilled — Feet
Total Depth of Hole 17 Feet
Core Recovered — %
Core Recovered — Ft.; — Diam. — In.
Soil Samples 1 3/8" In. Diam. 4 No.
Soil Samples — In. Diam. — No.
Water Table Depth dry

* Elevations provided by reviewer of draft report.

Depth		Method of Drilling and Type of Bit Used	INDEX	
From	To			
0	15	3/4" I.D. Hollow Stem Auger	Ground Water	Back of Page <u>4</u>
15	17	1 3/8" I.D. SPT Sampler	Boring Location Sketch	Back of Page <u>4</u>
			Overburden Record	Page <u>2-3</u>
			Rock Drilling	Page <u>—</u>
				Page <u>—</u>
				Page <u>—</u>
				Page <u>—</u>

Prepared by T.A. Braddox Field Data
Submitted by Atlantic Testing Labs, Ltd Lab. Data

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Fort Fairfield, ME. Page 2 of 4 Pages

Boring No. FD-86-13 Desig. C Diam. (Casing) 3 1/4"

FIELD LOG OF TEST BORING

Co-ordinates: X see Boring X Location Sketch

Elevation Top of Boring 379* M.S.L. Hammer Wt. 140# Boring Started 12 Mar 86
Total Overburden Drilled 17 Feet Hammer Drop 30"
Elevation Top of Rock — M.S.L. Casing Left — Boring Completed 12 Mar 86
Total Rock Drilled — Feet Subsurface Water Date — Page 4
Elevation Bottom of Boring 362* M.S.L. Obs. Well NO
Total Depth of Boring 17 Feet Drilled By Mark + Kevin Hawkins
Core Recovered — % No. Boxes — Mfg. Des. Drill truck mounted CHES5
Core Recovered — Ft. — Diam. — In. Inspected By: TA Beddor
Soil Samples 1 3/8 In. Diam. 4 No. Classification By: TA Beddor
Soil Samples — In. Diam. — No. Classification By: —

DEPTH		CORE/SAMPLE		BLOWS PER FT. CORRECTION	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
0.0'	1" = 2'	NO.	SIZE			
0.5'		S-1	1 3/8	REL 70%	75	Brown SILT, some cm & SAND, trace of GRAVEL, trace ORGANIC MATTER (grass) (moist, nonplastic) dense due to frost ML
5.0'						Similar Soils, loose, ML
		S-2	1 3/8	65%	2 7 6 5	
7.0'						
10.0'						

GENERAL REMARKS:

* Elevations provided by reviewer of draft report.

Boring moved so as not to crush pine seedlings at Mr. Novak's request.

Site Fort Fairfield, ME.					Boring No. FD-86-13		Page 3 of 4	
DEPTH		CORE/SAMPLE		BLOWS PER FT.	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS		
12.0'	1' 2'	NO.	SIZE	DEPTH RANGE			PERCENT RECOVERY	
12.0'		S-3	1 3/8	80%	2 3 3 5	3/4" I.D. Hollow Stem Auger Sampling by 1 3/8" I.D. by 2' long split spoon soil sampler Augering easy for full depth of boring	Brown m.f. SAND, trace SILT, trace GRAVEL (moist, non plastic) loose SP	
15.0'		S-4	1 3/8	75%	3 1 3 7	end of augering	Brown SILT, some cm.f. SAND, trace of GRAVEL (moist, non plastic) loose ML	
17.0'						bottom of hole at 17.0' as instructed in D.O.		

Page 4 of 4

Note: Depths are in feet below original ground

